



Massachusetts Water Resources Authority

*Quinapoxet Dam Removal  
Progress Update*

February 12, 2025



## Dam Removal Time-lapse





# River Restoration





## Restored Riverbed and Diversion Channel





## Restored Riverbed





## Riffles and Pools





## Looking Upstream





# FY25 Second Quarter Orange Notebook Highlights

MASSACHUSETTS WATER RESOURCES AUTHORITY


**Board of Directors Report**

on

**Key Indicators of MWRA Performance**

Second Quarter FY2025

| Q1 | Q2 | Q3 | Q4 |
|----|----|----|----|
|    |    |    |    |




Frederick A. Laskey, Executive Director  
David Coppes, Chief Operating Officer  
February 12, 2025







# Low precipitation continued in the beginning of the quarter



- Precipitation 16% below average
- Deer Island flow 22% below average
- New low flow records for October and November
- October monthly flow was second lowest since plant startup



# Impacts of drought on water supply





- Quabbin went down by 3.9 ft. and was at 85.5% capacity at the end of December – normal operating range
- On February 1<sup>st</sup> Quabbin levels dropped to below normal, with target rising to 85%



# Violations at Clinton Wastewater Treatment Plant


- Despite low precipitation, 12-month average flow was still over the limit in October
- Clinton effluent was over copper limits in October due to drought
  - Lack of dilution from normal inflow and infiltration during rainfall





# Molybdenum in Sludge Fertilizer Pellets

- Molybdenum (Mo) levels in fertilizer pellets in the 2<sup>nd</sup> quarter (42.7 mg/kg) exceeded MA land limits (40 mg/kg), but well below federal limit (75 mg/kg)
- This is **not a permit violation** since pellets are being distributed to other states
- Likely source is corrosion inhibitor in cooling towers





*Presentation to*

**MWRA Board of Directors**

*Fiscal Year 2026*


*Proposed Current Expense Budget*

February 12, 2025



## FY26 Proposed Current Expense Budget

*(\$s in million)*




**FY26 Proposed CEB:**  
Increase of \$21.6 million  
or 2.4% over FY25.



# FY26 Proposed CEB – Direct Expenses

## Direct Expenses by Category

(\$s in millions)




- **Direct Expenses:** Increase of \$8.5 million or 2.6% over FY25 driven by higher Other Services and Wages & Salaries, partially offset by lower Maintenance.
- **Other Services:** Increase of \$6.7 million or 19.8% over FY25 driven by Sludge Pelletization which increased by \$6.1 million or 26.9% primarily due to the addition of potential landfill disposal costs due to PFAS issues.
- **Wages & Salaries:** Increase of \$3.5 million or 2.6% over FY25. Funds 1,166.2 FTEs (1,168.0 FTEs in FY25). Includes a Vacancy Adjustment (reduction) of \$5.6 million.
- **Maintenance:** Decrease of \$3.3 million or 7.1% from FY25 driven by the completion of several large projects.



# FY26 Proposed CEB – Indirect Expenses

## Indirect Expenses by Category

(*\$s in millions*)




- **Indirect Expenses:** Increase of \$4.6 million or 6.2% over FY25 driven by higher Pension and Watershed Reimbursement, partially offset by lower HEEC.
- **Pension:** Increase of \$2.8 million or 13.3% over FY25. Includes Actuarially Determined Contribution (ADC) of \$18.3 million plus an additional \$5.8 million to assist with reaching full funding by 2030.
- **Watershed Reimbursement:** Increase of \$2.6 million or 8.0% over FY25 driven by higher Wages & Salaries, Fringe Benefits, Equipment, and PILOT. Funds 151 FTEs, with no vacancy adjustment included.
- **HEEC Payment:** Reduction of \$1.4 or 16.8% from FY25 based on the latest cost estimates.





## Capital Finance by Category

(\$s in millions)




- **Capital Finance:** Increase of \$8.4 million or 1.7% over FY25 driven by the structure of new and existing debt.
- **Variable Interest:** Assumes a rate of 4.5% (4.75% in FY25).
- **Defeasance:** Includes a \$15.0 million defeasance benefitting FY26-32.




# FY26 Proposed CEB - Long-Term Interest Rates

### Tax-Exempt Rates




### Taxable Interest Rates





# FY26 Proposed CEB - Short-Term Tax-Exempt Interest Rates

MWRA All-In Variable Rate Debt Cost






# FY26 Proposed CEB – Revenue by Category

## Revenue

(\$s in millions)




- **Total Revenues:** Increase of \$21.6 million or 2.4%.
- **Rate Revenue:** Increase of \$25.5 million or 3.0% over FY25 (previously projected at 3.3%).
- **Investment Income:** Short-term interest projected at 3.75% (5.0% in FY25).
- **Rate Stabilization:** No planned usage in FY26.



# FY26 Proposed CEB – Rate Projections (Combined)


**MWRA Combined Utilities  
Historical and Projected Rate Revenue Changes**





# FY26 Proposed CEB – Rate Projections (By Utility)

MWRA Water & Sewer Utilities  
Historical and Projected Rate Revenue Changes





## FY26 Proposed CEB – Next Steps

- Spring Revisit Process
- Provide briefings to Advisory Board Staff
- MWRA Public Hearing
- MWRA Board Hearing in May
- Staff anticipate FY26 Budget adoption in June



*Presentation to*

**MWRA Board of Directors**

***Combined Sewer Overflow Program  
Update***

February 12, 2025





# Completed Long Term Control Plan

## Types of CSO Control Projects

- Included a range of cost-effective projects (35 total) targeted to site specific control including:
  - System optimization
  - Sewer separation
  - Interceptor relief
  - Detention treatment facilities
  - Storage facilities
  - Upgrades to existing CSO facilities
- Total cost \$911 million (\$1.52 billion in today's dollars)
- When combined with related local community projects, that investment is over \$1 billion.






# System Wide CSO Reduction Since the Start of the CSO Program in the 1980s

## Prior Long Term Control Plan

- System wide improvements including the Charles, Alewife, Mystic resulted in significant reductions in CSO discharge since 1980s.



## System Wide CSO Reduction Since the 1980s

*\*Annual discharge volume based on the prior Typical Year*



# Variance Waters and Project Partners



**City of Somerville**




**City of Cambridge**



**Massachusetts  
Water Resources  
Authority (MWRA)**

<https://voice.somervillema.gov/joint-cso-planning>





# 2050 Design Storm CSO Activations and Discharge Volumes

## 2050 Typical Year

- A full year of rain data that best represents rain over time
- A representative "average" year for planning, as rain changes from year to year
- For the Updated CSO Control plan a new Typical Year was developed to reflect future climate conditions

## Design Storms

- 2050 5-Year 24-hour and 25-year 24-hour design storms were developed to reflect future climate conditions

| Receiving Water | Future Baseline Condition Model Results |                   |                           |                   |  |                   |                    |
|-----------------|---|-------------------|---------------------------|-------------------|--|-------------------|--------------------|
|                 | Activation Frequency                    |                   | CSO Discharge Volume (MG) |                   |  |                   |                    |
|                 | Prior Typical Year                      | 2050 Typical Year | Prior Typical Year        | 2050 Typical Year | 2050 Largest Storm in the Typical Year | 2050 5-year Storm | 2050 25-year Storm |
| Charles River   | 3                                       | 6                 | 7.9                       | 38.4              | 16.6                                   | 65.5              | 120.6              |
| Alewife Brook   | 8                                       | 13                | 9.9                       | 20.9              | 4.84                                   | 20.9              | 40.1               |
| Upper Mystic    | 2                                       | 8                 | 1.3                       | 29.3              | 10.5                                   | 17.4              | 27.2               |

## Updated CSO Control Plan Steps:

- ✓ 1) 2050 Typical Year & 2050 Design Storms
- ✓ 2) Unify Hydrologic & Hydraulic models
- ★ 3) **Create alternatives:**
  - a) Identify scenarios to evaluate CSOs
    - 2050 Typical Year
    - 2050 5-yr
    - 2050 25-yr
  - b) Combine CSO tools to develop various alternatives
  - c) Optimize regionally for each variance water

### Step 3b Zoom In: CSO Reduction Tools



Sewer Separation



Green Stormwater Infrastructure



Inflow/infiltration reduction




Storage



Conveyance

## Updated CSO Control Plan Steps:

- 
- 4) Develop conceptual layouts and preliminary cost estimates
  - 5) Compare alternatives using weighted criteria
  - 6) Assess Initially Preferred Alternative(s) for:
    - Financial Capability Assessment
      - Impact to rate payers
      - Implementation schedule
    - Compliance with Water Quality standards
      - What is the highest attainable use without a widespread economic or social impact?
  - 7) Develop Draft Updated CSO Control Plan(s)

## Step 5 Zoom In: Alternatives Evaluation Preliminary Criteria

Reduce/eliminate combined sewer overflows

---

Reduce flooding and flooding impacts

---

Reduce sanitary sewer overflows

---

Improve water quality

---

Rehabilitate old infrastructure (pipes, facilities)

---

Improve resilience of our infrastructure to future climate conditions

---

Improve service to low income and minority communities

---

Offers community co-benefits  
(e.g., green space, gathering space, heat reduction)

---

Minimize neighborhood disruption during construction

---

Minimize costs to ratepayers / taxpayers

---

Other criteria based on public feedback



# Interim Progress: Preliminary List of Potential Alternatives

| 2050 Typical Year                       | 2050 5-Year Storm                       | 2050 25-Year Storm                      |
|---|---|---|
| Integrated alternative by outfall       | -                                       | -                                       |
| Tunnel / Storage                        | Tunnel / Storage                        | Tunnel / Storage                        |
| Tunnel / Storage + Green Infrastructure | Tunnel / Storage + Green Infrastructure | Tunnel / Storage + Green Infrastructure |
| Sewer separation / Green Infrastructure | -                                       | -                                       |
| Hybrid                                  | Hybrid                                  | Hybrid                                  |

# Mystic River Sewer Separation

## City of Somerville - 2050 Typical Year CSO Control


### Potential Mystic River Projects

- Large trunk storm drains
- 5.5MG storage tank
- 0.5 MG storage tank
- 2 Storm drain outfalls
- 560 acres of localized sewer separation

Prelim. Estimated Cost:

~\$700 million \*

Prelim. Timeline: ~40 yrs




\*Costs include sewer separation of some areas tributary to both Alewife Brook and Mystic River. Costs estimated using 2024-dollar amounts and not escalated to construction period. Costs subject to refinement.



# Alewife Integrated Alternative: 2050 Typical Year CSO Control

- CAM401A: 2.1 MG storage
- CAM401B: 0.4 MG storage
- MWR003: 0.5 MG storage
- SOM001A: 264 acres separated + inline storage with throttles

Prelim. Estimated Cost: ~\$600 million



# Alewife Brook Storage Tunnel Alternative



**North Dorchester Bay Dewatering Pump Station**




**North Dorchester Bay Odor Control/Ventilation Facility**

| Alewife Brook Potential CSO Storage Tunnel Alternatives<br>(Tunnel Length: 1.4 Miles) |                     |                 |
|---|---------------------|-----------------|
| Level of CSO Control  | Storage Volume (MG) | Diameter (feet) |
| 2050 Typical Year   | 4.9                 | 11              |
| 2050 5 Year   | 20.6                | 22              |
| 2050 25 Year  | 41.6                | 32              |

**Preliminary Estimated Capital Costs Range from ~\$700M to ~\$1.7B\***

\*2024 dollars unescalated to construction period. Costs do not include land acquisition and may be further refined.

# Charles River Storage Tunnel Alternative



| Charles River Potential CSO Alternatives<br>(Tunnel Length: 4.5 Miles) |                     |                 |
|--|---------------------|-----------------|
| Level of Control   | Storage Volume (MG) | Diameter (feet) |
| 2050 Typical Year  | 17.8                | 12              |
| 2050 5 Year  | 71.9                | 24              |
| 2050 25 Year   | 132.1               | 32              |

**Preliminary Estimated Capital Costs Range from ~\$1.4B to ~\$2.3B\***

\*2024 dollars unescalated to construction period. Costs do not include land acquisition and may be further refined.

# Questions?





*Presentation to*

## **MWRA Board of Directors**

*HVAC Control System, Equipment and  
Fume Hood Replacement  
Preliminary Design, Final Design, Bidding and ESDC  
Deer Island Treatment Plant Contact 7110*

February 12, 2025



# Contract 7110 Improvements

- Design and Bidding, and ESDC Services to replace the following equipment:
  - Three central chillers in the Administration/Laboratory Building
    - Thirty-one Fume Hoods
    - Plant Wide Central HVAC Control System (approximately 10,000 points)
    - Approximately 53 HVAC units and 97 Fan Coil Units with associated field instrumentation
- Existing equipment is at the end of its useful life and/or obsolete





# HVAC Replacement History

- Original construction package advertised in 2018
  - Only one bid received which was approximately 80% higher than the engineer's Estimate
- Decision to split project into three separate contracts to increase competition
- Original designer proposal more than double original contract value
- Current scope developed. Based on previous design Issued in August 2024.



Typical HVAC Unit



## One Proposal Received

- Mott MacDonald proposed \$8,274,489.37 vs Engineer's Estimate of \$3,993,938
  - Significantly higher level of effort for design phase
  - Original design out of date: equipment and code changes
  - Bidding Services and ESDC within 10% of the engineer's estimate
- Alternatives to award considered
  - Do not anticipate better outcome
- Condition of equipment continues to degrade
- Significant costs and difficulty maintaining operation





# Administration/Lab Building Chillers




Existing Chillers



Rental Chiller



# Administration/Lab Building Chillers



Corroded Chilled  
Water Piping



Side View  
Insulation Around  
Shell



Rear Header



Front Header



# Administration/Lab Building Air Handling And Fume Hoods



Typical HVAC Unit




Typical Fume Hood



# HVAC Control Panels



Local Control Panel



Control System Front End Screen



Local Control Panel



# Contract 7110 Selection Committee Recommendation

- Staff recommend award to Mott MacDonald, LLC.
- Contract Price: \$8,274,489.37
- Contract Duration: 78 months





*Presentation to*

**MWRA Board of Directors**

*Digester Fixed Cover and Valve and Gate Replacement  
Clinton Treatment Plant  
Contract 7648*

February 12, 2025



# Digester Fixed Cover and Valve and Gate Replacement

Contract includes:

- Replacement of 40-foot diameter fixed concrete digester cover
- Replacement of existing stop plates and plug valves to each of the three clariflocculators
  - Concrete repair and coating work in the distribution box
- New influent sampler enclosure





# Bid Results

| Bidder                                    | Bid Price           |
|---|---------------------|
| <i>Engineer's Estimate</i>                | \$6,270,435         |
| <b>Walsh Construction Company II, LLC</b> | <b>\$6,974,750*</b> |
| Wes Construction Corp                     | \$8,685,000*        |

- Includes \$500k allowance for waterproofing filed sub-bid

- Contract Term: 540 calendar days
- Adjusted contract amount: \$7,013,650
- Staff Recommend award to Walsh Construction Company II, LLC







*Presentation to:*


**MWRA Board of Directors**

*Northern Extra High Pressure Zone Improvements  
CP2, Arlington and Lexington), Contract 7725*

February 12, 2025



# Project Schematic





# Contract 7725 Bid Results

| Bidders                    | Bid Amount             |
|----------------------------|------------------------|
| <i>Engineer's Estimate</i> | <i>\$22,833,825.00</i> |
| RJV Construction Corp.     | \$26,846,000.00        |
| P. Gioioso & Sons Inc.     | \$27,445,000.00        |
| Albanese D&S, Inc.         | \$27,844,000.00        |
| Albanese Bros. Inc.        | \$33,954,590.00        |
| D'Allessandro Corp.        | \$41,496,482.00        |